SR

SOLAR RAYS ENERGY SOLUTIONS LLP

Clean solar. Smarter savings.

Solar Power Proposal

5.0 kW On-Grid Solar Power Project

PREPARED FOR	QUOTATION	DATE
Sample Customer	SRES/2026-27/ON/0001	05/10/2026

Dear Customer,

Solar Rays Energy Solutions LLP designs, deploys and maintains high-performance rooftop solar systems focused on long-term savings, reliable engineering and energy independence.

We are pleased to submit our proposal based on the project requirements shared with us. The proposed solution includes engineering, supply, installation, testing and commissioning of the solar power system, subject to the final site survey and agreed commercial terms.

Project Snapshot

System Type	On-Grid
Plant Capacity	5.0 kW
Phase	Single Phase
Solar Module	Waaree - 580 Wp
No. of Modules	9
Inverter	Luminous - 5.0 kW

Our Scope

• System sizing and engineering based on the agreed capacity and site conditions.

• Supply of solar modules, inverter, mounting structure, protection systems, cables and standard accessories as listed in the BOQ.

• Installation, testing and commissioning of the solar power plant.

• Support for net-metering / documentation where included in the commercial scope.

• After-sales support as per applicable product warranties and the final order terms.

Commercial Quotation

5.0 kW On-Grid Solar Power Project

Quotation Ref.	SRES/2026-27/ON/0001
Quotation Date	05/10/2026
Customer	Sample Customer
Mobile	98XXXXXXXX
Address	Indira Nagar, Lucknow, Uttar Pradesh

Bill of Quantities (BOQ)

S.No.	Description	Make	Unit	Qty
1	Solar PV array - 5 kW system using 580 Wp modules	Waaree	Wp	9
2	On-Grid solar inverter	Luminous	kW	5.0
3	Module mounting structure with required fasteners for rooftop installation	GI / HDG	Set	1
4	ACDB / DCDB, surge protection and required electrical protection	As per approved design	Set	1
5	AC/DC cables, conduit, junctions, connectors and standard accessories	As per approved design	Lot	1
6	Earthing system and lightning protection	As per approved design	Set	1
7	Installation, testing and commissioning	Solar Rays	Job	1

Commercial Summary	
Basic Amount	INR 250,000.00
Discount	INR 0.00
Taxable Value	INR 250,000.00
GST @ 5%	INR 12,500.00
Other Charges	INR 0.00
Grand Total	INR 262,500.00
Central Subsidy	INR 78,000.00
State Subsidy	INR 0.00
Total Indicative Subsidy	INR 78,000.00
Effective Customer Cost	INR 184,500.00

Subsidy is indicative and subject to scheme eligibility, prevailing government rules, portal approval and successful completion of the required process.

Terms & Conditions

• Quotation validity: 10 days from date of issue.

• Payment terms: 100% advance, or as mutually agreed in the final purchase order.

• Delivery, installation & commissioning: Within 1-2 weeks from confirmed order and advance, subject to site readiness.

• Net-metering: Included / assisted

• Warranty: As per OEM warranty and final order terms.

Detailed Material Specification

S.No.	Component	Description	Quantity	Make
1	Solar PV Modules	Bifacial Mono PERC / TOPCon modules, approx. 580 Wp each	9 Nos.	Waaree
2	Inverter / PCU	On-Grid inverter, Single Phase	5.0 kW / 1 No.	Luminous
3	DC Distribution Box	IP65 enclosure with DC protection / SPD / fuses as required	1 Set	As per approved design
4	AC Distribution Box	IP65 enclosure with MCB/MCCB, SPD and protection as required	1 Set	As per approved design
5	AC Cable	Copper / aluminium cable sized as per approved electrical design	As per system	Standard approved make
6	Interconnecting DC Cable	Solar DC cable, UV resistant and suitably rated	As per system	Standard approved make
7	Module Mounting Structure	GI / HDG structure designed for site conditions and module layout	As per module layout	GI / HDG
8	Earthing Cable	Copper / GI earthing conductor sized as per design	As per system	Standard approved make
9	Earthing	Earth electrodes / rods with required accessories	3 Sets (typical)	Standard approved make
10	Lightning Arrestor	Conventional lightning protection with supporting arrangement	1 Set	Standard approved make

Note: Final makes, models and quantities are subject to approved design, site survey, availability and the mutually accepted purchase order. Any deviation requested by the customer may affect price and delivery.

Company Details

Company	SOLAR RAYS ENERGY SOLUTIONS LLP
GSTIN	
Website	https://solarraysenergy.com/
Email	
Phone	99365 33017 / 90050 93327
Address	

Thank you for the opportunity to submit this proposal.

For SOLAR RAYS ENERGY SOLUTIONS LLP

Authorized Signatory